

25-25-16W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE PETROLEUM CO., INC.
Farm- Mellon No. 1

SEC. 25 T. 25 R. 16W
150' W of C SW NE

Total Depth. 4469'
Comm. 6-28-62 Comp. 7-11-62
Shot or Treated.
Contractor. Leben Drilling, Inc.
Issued. 11-10-62

County Edwards
KANSAS



CASING:

8 5/8" 372' cem w/250 sx.
5 1/2" 4469'

Elevation. 2053' RR

Production. 51 BOPD & 5 BWPD

Figures Indicate Bottom of Formations.

sand & clay	120
shale & shells	320
shale	373
red bed & shale	1000
anhydrite	1105
shale	2010
shale & lime	2215
lime & shells	2295
lime	2425
lime & shale	3075
lime	3194
lime & shale	3523
lime	3776
shale & lime	3844
lime	4195
lime & shale	4250
lime	4320
conglomerate	4382
lime	4400
shale	4438
Viola lime	4463
lime	4469 RTD
Total Depth	

TOPS: LOG

Heebner	3600
Toronto	3716
Douglas	3734
Brown Lime	3842
Lansing	3857
Base Kansas City	4129
Cherokee Shale	4285
Cherokee Sand	4293
Cherty Conglomerate	4313
Kinderhook	4368
Viola	4428