

KANSAS DRILLERS LOG

Sampled on 6/16/78

API No. 15 — 047 — 20116
County Number

Operator

Imperial Oil Co.

Address

720 Fourth Financial Ctr. Wichita, KS 67202

Well No.

1-17 Lease Name

Baird

Footage Location

990 feet from (X) (S) line 990 feet from (E) (W) line

Principal Contractor

B&N Drilling Co.

Geologist

E. B. Donnelly

Spud Date

11/10/78

Total Depth

4662 RTD

P.B.T.D.

Date Completed

11/22/78


Oil Purchaser

OCT 17
S. 17 T. 25S R. 18W
Loc. C NW SE SE

County Edwards

640 Acres

N



Locate well correctly

Elev.: Gr. 2189

DF 2197 KB 2199

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$ "	8 5/8"	24#	445'	Lite Wt. Common	200 125	3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at		

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used		Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)		
RATE OF PRODUCTION PER 24 HOURS		Oil bbls.	Gas MCF	Water bbls.
Disposition of gas (vented, used on lease or sold)		Producing interval(s)		

CFPB

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Imperial Oil Company

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.	Lease Name	
1-17	BAIRD	Dry Hole

S 17 T 25 R 18 X
W

Edwards

WELL LOG


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 4448-80' 30/45/30/45 Rec. 7' Mud ISIP: 51# FSIP: 42# IFP: 34-34# FFP: 34-34#				Elec. Log
DST #2 4585-4625' 30/45/30/45 Rec. 5' Mud ISIP: 59# IFP: 34-34# FSIP: 42# FFP: 34-34#			Herington	2438 (-239)
DST #3 4617-62' 60/60/65/70 Rec. 685' Muddy SW ISIP: 1228# IFP: 51-279# FSIP: 1126# FFP: 288-364#			Council Grove	2783 (-58)
			Beatie Gas Zn	2893 (-68)
			Cottonwood	2930 (-7)
			Foraker	3124 (-915)
			Wabaunsee	3276 (-1027)
			Stotler	3359 (-11)
			Howard	3562 (-13)
			Heebner	3953 (-17)
			Lansing	4096 (-1897)
			Base/KC	4463 (-2264)
			Marmaton	4476 (-2277)
			Cherokee Sh.	4585 (-2386)
			Mississippi	4649 (-2450)

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



Signature

Attorney-in-Fact

Title

November 30, 1978

Date