

KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

API No. 15 — 047 — 20,603
County Number

PI

Operator

Cinco Exploration Co.

Address

Box 3723 Victoria, Texas 77901

Well No.

#1

Lease Name

Lancaster

Footage Location

660

feet from (N) (S) line

660

feet from (E) (W) line

Principal Contractor

H-30 Inc.

Geologist

Charles B. Spradlin

Spud Date

12-21-79

Total Depth

4700

P.B.T.D.

Date Completed

1-5-80

Oil Purchaser


State Geological Survey
S. 11 T. 25S R. 19 W
WICHITA, KANSAS

Loc. C SE SE

County Edwards

640 Acres

N



Locate well correctly

2202

Elev.: Gr.

2210

2212

DF

KB

Directional Deviation 3150-3/4° CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	461	Class "H"	150	3% CA C/2
					50/50 Pozmix	250	3% CA C/2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	SCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator CINCO EXPLORATION COMPANY DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name Lancaster Dry hole

S 11 T ~~X~~ SR 19 W P/A 1-5-80

(DRL)

255


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Formation		Subsea		
Anydrite	1317	+ 895	DST #1	
Base Florence	2695	- 483	4423-73	
Neva	2996	- 784	30/30/30/60	
Foraker	3134	- 922	IF 40#/48#	
Wabaunsee	3234	-1022	FF 56#/65#	
Statler	3370	-1158	ISI 1469#	
Tarkio	3420	-1208	FSI 1517#	
Howard	3562	-1350	Recovered 50'	Drilling Mud.
Topeka	3596	-1384		
Heebner	3946	-1734	DST #2	
Brown Lime	4061	-1849	4614-40	
Lansing	4070	-1858	30/40/60/90	
Base Kansas City	4426	-2214	IF 32#/40#	FF 40#/65#
Marmaton	4453	-2241	ISI 1334#	
Cherokee	4562	-2351	FSI 1374#	
Mississippian	4623	-2411	Recovered 60'	Slight
Kinderhook	4692	-2480	gas cut mud	
TD	4700	-2488	Pipe full of gas	
			DST #3	
			4640-4669	
			60/120/180/120	
Ran Schlumberger Dual Ind. El Laterolog and compensated GR DN Log			IF 32#/40#, FF 40#/48#	
			ISI-242# FSI 404#	
No Oil or gas shows P/A	1-5-80		Recovered 500' gas in pipe	
			45' gas cut mud.	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received		
	MELVIN KLOTZMAN	Signature
	Petroleum Consultant	
	8-18-80	Title
	Date	

10618