

**Abercrombie Drilling INC.**

15-057-20539

WEISS 'B' #1

**DST#1 4146'-4174' (misrun)**

Hit solid bridge at 850'.

**DST #2 4146'-4174'**

30-45-60-45

Weak blow built to 8" (1st open)

Built to 3" (2nd open)

Rec: 180' MW

270' SW

IFP 53-106 ISIP 1241#

FFP 170-213 FSIP 1219#

Strap at 4174': Strap 4.06' long.

**Electric Log Tops**

Heebner 4010' (-1721')

BR LM 4115' (-1826')

Lansing 4126' (-1837')

B/KC 4516' (-2227')

Marmaton 4524' (-2235')

Ft. Scott 4639' (-2350')

U. Cher. Sh. 4653' (-2364')

L. Cher. Sh. 4686' (-2397')

Warsaw 4747' (-2458')

Osage 4765' (-2476')

RTD 4850'

LTD 4856'

**DST #3 4646'-4680' (Upper Cher. Sh.)**

30-45-60-45

Weak blow throughout

Rec: 15' GCM

IFP 42-42 ISIP 53#

FFP 42-42 FSIP 53#

**DST#4 4678'-4712'**

30-30-30-30

1st open weak 1/8" blow, died in 20 minutes

2nd open no blow, flush tool no help.

Rec: 10' mud

IFP 53-53 ISIP 53

FFP 53-53 FSIP 53

113°-BHP

**DST #5 4712'-4753'**

30-30-30-30

Weak blow died

Rec: 10' OSM

IFP 25-31 ISIP 90

FFP43-45 FSIP 84

**DST #6 4752'-4761'**

1st blow off bottom 25", 2nd blow off bottom 27"

Rec: 5' CO, 550' OSW

IFP 26-170 ISIP 1513

FFP 176-313 FSIP 1505

Chlorides

32,000 ppm

RECEIVED  
KANSAS COMP CORP  
1996 APR 23 A 11: 17