

2-25-21W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ARTNELL COMPANY
Farm- Stegman No. 1

SEC. 2 T. 25 R. 21W
NW NW SW

Total Depth. 4754 ft
Comm. 12-18-59 Comp. 1-1-60
Shot or Treated.
Contractor. Strata Drlg. Co.
Issued. 2-20-60

County Ford
KANSAS



Elevation. 2285 ft

Production. Dry

CASING:

12" 350 ft
8 5/8" 355 ft cem.w/190 sx.

Figures indicate Bottom of Formations.

clay & shale	220
shale & shells	355
shale	485
sand	650
shale & sand streaks	1135
shale & lime	1960
lime & shale	2665
lime	2920
lime & shale	3855
lime	3983
lime & shale	4045
lime	4645
lime & shale	4690
lime	4725
chert & lime	4754
Total Depth	

TOPS: SCOUT

Heebner	3983
Brown Lime	4083
Lansing	4092
Wormaton	4480
Mississippi	4698

DST #1 4708-4725' Recovered 610' slightly
oil cut salt water. IFP 115 lbs.
FFP 305 lbs. BHP 1385 lbs. in 30
minutes.