

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

503 East Murdock,

Wichita, Kansas

8-25-21W


Company- HONAKER-DAVIS DRILLING CO., et al
 Farm- Seward No. 1

SEC. 8 T. 25 R. 21W
 NW NW NE

Total Depth. 4803
 Comm. 3-2-57 Comp. 3-18-57
 Shot or Treated.
 Contractor. Honaker-Davis Drlg. Co.
 Issued. 4-27-57

County Ford

KANSAS



CASING:
 8 5/8" 350' cem w/250 sx.

Elevation. 2338 R.B.

Production. Dry

Figures indicate Bottom of Formations.

top soil, sand	160
sandstone	225
redbed, blue shale	313
shale blue	346
shale, red bed	902
red bed	907
sand, red bed	1300
red bed	1450
anhydrite	1485
shale, shells	1985
lime, shale	2400
lime	2540
lime, shale	4185
lime, shale, chert	4286
lime, shale	4407
lime	4511
lime, chert	4543
lime	4660
lime, shale	4714
lime, chert, shale	4754
lime, shale	4775
lime, chert	4803
Total Depth	

Tops: Time Log, Samples & Hall.

Heebner	4018
Brown lime	4114
Lansing-K. C.	4124
Marmaton	4516
Cherokee	4646
Conglomerate	4717
Mississippian	4733

Drill Stem Tests by Halliburton

4740-4758 Tool open 20" - 55" - 20"
 Blow: Weak 26" - weak 24"
 Recovery: 120' VSGCM
 Pressures: IBHP 685#, FBHP 720#
 IFP 35#.

4758-4775 Tool open : 20" - 90" - 20"
 Blow: Weak fo fair
 Recovery: 330' VSGCMSW
 Pressures: IBHP 1470#, FBHP 1300#
 IFP 35#, FFP 145#.