

33-25-21W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL CO.
Farm- Torline No. 1

SEC. 33 T. 25 R. 21W
C NE SE

Total Depth. 4792'
Comm. 7-24-61 Comp. 8-7-61
Shot or Treated.
Contractor. Imperial Oil of Kans.
Issued. 11-11-61

County Ford
KANSAS



Elevation. 2328' KB

Production. 290 BOPD

CASING:

8 5/8" 248' cem w/175 sx.
5 1/2" 4781' cem w/125 sx.

Figures Indicate Bottom of Formations.

shale & sand	248
sand & shells	660
sand & shale	1370
Anhydrite	1395
shale & shells	2270
lime & shale	4209
lime	4785 RTD
lime	4792
Total Depth	

TOPS:	SAMPLE	ELECTRIC
Heebner	4028	4035
Brown Lime	4142	4147
Lansing	4151	4155
Cherokee Shale	4640	4646
Mississippian (Warsaw)	4779	4786

DST #1 4689-4707', op 1/2 hr, rec. 10'
rotary mud. ICIP 1455#/30 mins, IF 0#,
FF 0#, BHP 155#/30 mins.

DST #2 4706-30', op 2 hrs, gas surf. in
22 mins, rec. 1500' muddy gassy oil,
ICIP 1545#/30 mins, IF 150#, FF 775#,
BHP 1425#/30 mins.

DST #3 4773-85', op 1 hr, gas surf in 2 mins.
Gauge 1,000,000 CFGPD/5 mins, TSTM in 10 min.
Rec. 100' very heavily oil & gas cut mud,
500' clean oil. ICIP 1350#/20 mins,
IF 100#, FF 100#, BHP 1045#/20 mins.