

33-25-21W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- IMPERIAL OIL CO.
Farm- Torline No. 2

SEC. 33 T. 25 R. 21W
C SE SE

Total Depth. 4817'
Comm. 11-20-61 Comp. 12-7-61
Shot or Treated.
Contractor.
Issued. 3-3-62

County Ford

KANSAS



Elevation. 2327' KB

CASING:
8 5/8" 215' cem w/175 sx.

Production. Dry

Figures Indicate Bottom of Formations.

surface clay & sand	140
sand & shale	820
Anhydrite	860
shale & shells	1430
shale & pyrite	1700
shale & shells	2330
lime & shale	2975
lime	3280
lime & shale	3974
lime & chalk	4055
lime & shale	4170
lime	4515
lime & chert	4542
lime	4817 RTD
Total Depth	

TOPS:	
Heebner	4034
Brown Lime	4144
Lansing	4154
Base Kansas City	4544
Cherokee Shale	4640
Mississippian	4787
Osage	4813

DST #1 4716-60', op 1 hr, rec. 10' mud.
BHP 0#.

DST #2 4733-89', op 2 hrs, rec. 600' gas
cut muddy water. ICIP 1500#, IFP 75#,
FFP 260#, FBHP 1460#/30 mins.