

35-25-21W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- IMPERIAL OIL COMPANY
Farm- Israel No. 1

SEC. 35 T. 25 R. 21W
C NE SE

Total Depth. 4821'

Comm. 11-22-61

Comp. 12-7-61


Shot or Treated.

Contractor.

Issued. 3-3-62

County Ford

KANSAS



Elevation. 2282' KB

CASING:

8 5/8" 217' cem w/175 ex.

Production. Dry

Figures Indicate Bottom of Formations.

shale & sand	230
shale & shells	765
Anhydrite	795
shale & shells	2265
shale & lime	4270
lime	4821 RED
Total Depth	

TOPS:

Heebner	3997
Brown Lime	4103
Lansing	4115
Base Kansas City	4504
Cherokee Shale	4614
Mississippian	4764
Osage	4802

DST #1 4611-4705', op ½ hr, rec. 30'
mud, ICIP 320#, FBHP 0#/20 mins.

DST #2 4742-50', op 2 hrs, rec. 30' very
slightly oil & gas cut mud. ICIP 1430#,
IFP 0#, FFP 0#, FBHP 1190#/30 mins.

DST #3 4750-55', op ½ hr, rec. 10' mud.
ICIP 1300#, IFP 0#, FFP 0#, FBHP 0#/20 mins.

DST #4 4755-67', op ½ hr, rec. 30' mud.
ICIP 1370#, IFP 0#, FFP 0#, FBHP 1360#/30 mins.

DST #5 4767-80', op 2 hrs, rec. 1680' salt
water. ICIP 1500#, IFP 70#, FFP 720#,
FBHP 1430#/30 mins.