

**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

Prepared For: **Vincent Oil Corp**

155 N Market
Suite 700
Wichita, KS 67202

ATTN: Jim Hall

33-25s-24w Ford,KS

Bleumer #2-33

Start Date: 2010.10.12 @ 22:28:00

End Date: 2010.10.13 @ 06:57:20

Job Ticket #: 39462 DST #: 1

KCC

JAN 31 2011

CONFIDENTIAL

RECEIVED

FEB 01 2011

KCC WICHITA

Trilobite Testing, Inc

PO Box 1733 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



**TRILOBITE
TESTING, INC**

DRILL STEM TEST REPORT

Vincent Oil Corp

155 N Market
Suite 700
Wichita, KS 67202
ATTN: Jim Hall

Bleumer #2-33

33-25s-24w Ford, KS

Job Ticket: 39462

DST#: 1

Test Start: 2010.10.12 @ 22:28:00

GENERAL INFORMATION:

Formation: **Conglomerate**

Deviated: **No** Whipstock: **ft (KB)**

Time Tool Opened: 01:10:10

Time Test Ended: 06:57:20

Test Type: **Conventional Bottom Hole**

Tester: **Jake Fahrenbruch**

Unit No: **43**

Interval: **4890.00 ft (KB) To 4929.00 ft (KB) (TVD)**

Total Depth: **4929.00 ft (KB) (TVD)**

Hole Diameter: **7.88 inches** Hole Condition: **Good**

Reference Elevations: **2515.00 ft (KB)**

2506.00 ft (CF)

KB to GR/CF: **9.00 ft**

Serial #: 8648 **Inside**

Press@RunDepth: **26.82 psig @ 4891.00 ft (KB)**

Start Date: **2010.10.12**

End Date:

2010.10.13

Start Time: **22:28:05**

End Time:

06:57:20


Capacity: **8000.00 psig**

Last Calib.: **2010.10.13**

Time On Btm: **2010.10.13 @ 01:08:00**

Time Off Btm: **2010.10.13 @ 04:18:39**

TEST COMMENT: IF: Weak blow @ .5", slowly died off.
ISI: No blow.
FF: No blow, flushed tool, no blow.
FSI: No blow.



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2437.90	117.30	Initial Hydro-static
3	24.78	116.84	Open To Flow (1)
30	26.40	117.63	Shut-In(1)
92	1385.00	118.82	End Shut-In(1)
93	26.84	118.42	Open To Flow (2)
122	26.82	119.23	Shut-In(2)
189	1283.91	120.13	End Shut-In(2)
191	2416.28	120.26	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
15.00	Drilling Mud 100% m	0.21

Gas Rates

Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Vincent Oil Corp
155 N Market
Suite 700
Wichita, KS 67202
ATTN: Jim Hall

Bleumer #2-33

33-25s-24w Ford, KS

Job Ticket: 39462


DST#: 1

Test Start: 2010.10.12 @ 22:28:00

Tool Information

Drill Pipe:	Length: 4877.00 ft	Diameter: 3.80 inches	Volume: 68.41 bbl	Tool Weight: 2500.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer: 30000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight to Pull Loose: 125000.0 lb
			Total Volume: 68.41 bbl	Tool Chased 3.00 ft
Drill Pipe Above KB:	15.00 ft			String Weight: Initial 85000.00 lb
Depth to Top Packer:	4890.00 ft			Final 85000.00 lb
Depth to Bottom Packer:	ft			
Interval between Packers:	39.00 ft			
Tool Length:	67.00 ft			
Number of Packers:	2	Diameter: 6.75 inches		
Tool Comments:				

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Shut In Tool	5.00			4867.00	
Hydraulic tool	5.00			4872.00	
Jars	5.00			4877.00	
Safety Joint	3.00			4880.00	
Packer	5.00			4885.00	28.00 Bottom Of Top Packer
Packer	5.00			4890.00	
Stubb	1.00			4891.00	
Recorder	0.00	8648	Inside	4891.00	
Recorder	0.00	6799	Outside	4891.00	
Perforations	33.00			4924.00	
Bullnose	5.00			4929.00	39.00 Bottom Packers & Anchor
Total Tool Length:		67.00			



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

FLUID SUMMARY

Vincent Oil Corp

Bleumer #2-33

155 N Market
Suite 700
Wichita, KS 67202
ATTN: Jim Hall

33-25s-24w Ford, KS

Job Ticket: 39462

DST#: 1

Test Start: 2010.10.12 @ 22:28:00

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 52.00 sec/qt

Cushion Volume:

bbl

Water Loss: 8.39 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 3700.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
15.00	Drilling Mud 100% _m	0.210

Total Length: 15.00 ft

Total Volume: 0.210 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:

Serial #: 8648

Inside

Vincent Oil Corp

33-25s-24w Ford,KS

DST Test Number: 1

