

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-669-26024

KANSAS DRILLERS LOG

API No. 15 — 069 — 20,024
County Number

Operator
Gear Petroleum Company

Address
1325 Vickers KSB&T Building Wichita, Kansas 67202

Well No. # 1 Lease Name
Eitzen


Footage Location
330 feet from (N) (S) line 2310 feet from (E) (W) line

Principal Contractor
Slawson Drilling Company Geologist
Benny Singleton

Spud Date
4-5-78 Total Depth
5200' P.B.T.D.
N/A

Date Completed
4-15-78 Oil Purchaser
N/A

S. 28 T. 25 R. 27 W
Loc. SW SW SE
County Gray



Elev.: Gr. 2727'
Locate well correctly

DF 2730' KB 2732'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	28#	435'	60/40 Pozmix	300	2% Gel, 3% CaCl

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement
N/A	N/A	N/A

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A

TUBING RECORD

Size	Setting depth	Packer set at
N/A	N/A	N/A

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
N/A	N/A

INITIAL PRODUCTION

Date of first production N/A	Producing method (flowing, pumping, gas lift, etc.) N/A			
RATE OF PRODUCTION PER 24 HOURS	Oil N/A bbls.	Gas N/A MCF	Water N/A bbls.	Gas-oil ratio N/A CFPB
Disposition of gas (vented, used on lease or sold) N/A			Producing interval (s) N/A	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Gear Petroleum Co.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Eitzen	Dry Hole
S 28 T 25SR 27W E W		

WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.	SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.
--	---

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
LOG TOPS				
Winfield	2748	-16		
B/Florence	2989	-257		
Neva	3203	-471		
Stotler	3555	-823		
Howard	3703	-971		
Topeka	3774	-1042		
Heebner	4133	-1401		
Lansing	4220	-1488		
Cherokee Shale	4801	-2069		
Cherokee Sand	4907	-2215		
St. Louis	4947	-2215		
Spergen	5002	-2220		
LTD	5195	-2463		
RTD	5200	-2468		
RAN ELECTRIC LOGS.				
DST #1, 4919-54', 30-30-30-30", weak blow/7", Rec 15' M, SIP 120-109#, FP 43-55#.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	R. James Gear Signature
	Owner
	Title
	May 12, 1978
	Date