



Natural Gas • Crude Oil
Exploration & Production

Computer Inventoried

McCOY PETROLEUM CORPORATION

3017 North Cypress
Wichita, Kansas 67226-4003
316-636-2737

API #15-069-20257

John Roger McCoy
President

Kevin McCoy
Vice-President

Harvey H. McCoy
Vice-President

Keith McCoy
Treasurer

COPY

McCoy Petroleum Corporation
KDRW #1-30
C E/2 SW/4 Section 30-25S-29W
Gray County, Kansas

Page 2 ACO-1

DST #1 4855-4884' (St. Louis)

Open 30", S.I. 60", Open 90", S.I. 120"

Weak 1/4" blow on 1st open period.

Very weak 1/8" blow on 2nd open period.

Recovered 50' of gas in the pipe,

40' of slightly oil and gas cut mud. (5% gas, 3% oil, 92% mud)

FP 32-35# 37-42#

ISIP 130# FSIP 121#

DST #2 4722-4752' (Cherokee)

Open 30", S.I. 60", Open 90", S.I. 120"

Strong blow, OBB/1" on 1st open period. (BBBB/25")

Gas to the surface in 3 minutes on 2nd open period.

Gauge 25,100 CFGPD in 10",

" 4,760 CFGPD in 20",

" TSTM through remainder of test.

Recovered 820' of total fluid as follows:

470' of clean oil, (31 degree gravity)

200' of gassy mud cut oil, (40% gas, 30% oil, 30% mud)

150' of heavily oil and gas cut mud. (20% gas, 25% oil, 55% mud)

FP 86-154# 177-322#

ISIP 1228# FSIP 1158#

ELECTRIC LOG TOPS

Heebner	4004 (-1300)
Lansing	4094 (-1390)
Marmaton	4541 (-1837)
Pawnee	4615 (-1911)
Cherokee	4654 (-1950)
St. Genevieve	4793 (-2089)
St. Louis	4857 (-2153)
St. Louis "B" porosity	4866 (-2162)
LTD	4986 (-2282)

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1995

CONSERVATION DIVISION
WICHITA, KANSAS