

MC CANDLESS

Form 113 50M 4-49-47450-D

State Kansas County StaffordSec. 29 Twp. 25 Rng. 13W Elev. 1960Company Sun OilWell No. 1 Name McCandlessLocation SW SW SW

Feet from lines: N. S. E. W.

Spud 5-24-49 Completed 7-27-49T. D. 4636 Casing 8" 834; 5" 3995

Comp. Perf.

Pay

I. P. T. A.

Choke T. P. C. P.

G. O. R. Grvty.

DATE	REMARKS
7-27-49	Anh 829, Heeb 3540, BrL 3696
DWLE	Miss K180, V1 4205, SSH 4276

DATE

REMARKS

DIVE

REMARKS

Arb 4320, DST 3861-81/60/150'

OCM, DST 3881-3995/75/330' mud

& 240' W. & 4295-4305, rec 10'

sd sh strks, DST 4393-4405/

56/10' mud, & 4305-10 rec 4' sd

& sdy sh, SSO, top 1', TD 4636

DP 3955, 64 & 3914-30, 500A,

Swb 125'0, 2 BOPH, PB 3909

36 & 3899-3908 SFO, 500A, Swb

2 BOPH PB 3895, 56 & 3880-94

FU 200'0 some gas, 1000A, Swb

5 BOPH, PB 3876, 60 & 3860-75

Swb 6 BO & 1 BW/2 hr, 1000A,

Swb 6.8 BOPH, drove plug to btm, Swb

34 BO & 51 BW in 21 hr, PB 3876

to test. 60 & 3860-75, Swb 6 BO & 1

BW 12 hr, 1000A, Swb 34 BO & 51 BW/

24, Swb 27 BO & 39 BW/10, Swb 9 BO

& 22 BW/6 hr, Sqz 3860-75, DO 3900

NS, Sqz all perfs 280 & 3860-3950

14 GSW PH/4, 500 A, Swb 4 BWPH tr

VSSO 19 hr, sqz all perfs, Clo 3888

64 & 3862-78, 1500A, Swb 1 BO & 7

BWPH.

T. A.

LOW 113 20M 4-40-1420-D

NO COUNTERS