

CONFIDENTIAL

OCT 23 1981


KANSAS DRILLERS LOG

State Geological Survey
WICHITA BRANCH

S. 29 T. 25 R. 29W E W

Loc. C SW NE

County Gray

640 Acres
N

RELEASED

Date: APR 30 1982

FROM CONFIDENTIAL

Elev.: Gr.

2684

DF 2686

KB 2689

API No. 15 — 069 — 20039
County Number

Operator

DONALD C. SLAWSON

Address

200 Douglas Building Wichita, Kansas 67202

Well No.

1

Lease Name

Renick 'V'

Footage Location

1980' feet from (N) (S) line 2000' feet from (E) (W) line

Principal Contractor

Slawson Drilling Company, Inc.

Geologist

Raymond Palmer

Spud Date

March 24, 1979

Total Depth

5060'

P.B.T.D.

NA

Date Completed

April 5, 1979

Oil Purchaser

NA

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	23#	410'	60/40 poz	325 sx	2% gel; 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)		
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator DONALD C. SLAWSON		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1	Lease Name Renick 'Y'		Dry Hole
S 29 T 25 R 29W E W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME DEPTH
0 - 325 Sand and shale 325 - 415 Shale 415 - 675 Shale, chalk and sand 675 - 1120 Shale and sand 1120 - 1260 Shale and shells 1260 - 1445 Sand 1445 - 1721 Shale and shell with sand 1721 - 1760 Anhydrite 1760 - 1768 Shale 1768 - 2470 Shale and sand 2470 - 2500 Shale-Anhydrite 2500 - 2625 Lime and shells 2625 - 4265 Lime and shale 4265 - 4635 Lime 4635 - 4803 Lime and shale 4803 - 4840 Lime 4840 - 4995 Miss. 4995 - 5060 Miss.-Lime 5060 RTD			<u>LOG TOPS</u> B/ANH 1781 (+908) KRI 2594 (+95) HEEB 3996 (-1307) LANS 4042 (-1353) STK 4415 (-1726) U/CHER 4646 (-1957) L/CHER 4678 (-1999) ST. GEN 4781 (-2092) ST. LOUIS 4816 (-2127) SPERG 5024 (-2335) LTD 5060 (-2371)
DST #1 2586-2625 (KRI) 30-60-45-75, WKB, Rec. 35' M, No Gas. IFP 26-53#, ISIP 210#, FFP 53-53#, FSIP 236#, HP 1248-1248#, BHT 85°.			
DST #2 4764-4803 (ST.GEN) 30-30-30-30, V-Wk-B/died 15", Rec. 15' Drlg Mud. IFP 21-30#, ISIP 44#, FFP 35-35#, FSIP 50#, 126°. HP 2251-2251#.			
DST #3 4822-4840 (ST.LOUIS) 30-30-30-30, V-WKB, Rec. 20' M, sli scum oil. IFP 30-30#, ISIP 383#, FFP 35-38#, FSIP 177#, 125°. HP 2301-2295#.			
DST #4 4830-4855 (ST.LOUIS) 30-60-45-75, Wk incr to strg B/3". Rec. 3358' GIP, 173' GCO, 186' GCMO, IFP 59-103#, ISIP 1087#, FFP 133-177#, FSIP 934#, 126°. HP 2384-2355#.			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature R.J. THATCHER - Engineer Title April 22, 1979 Date		

JUL

WELL LOG

29.25.29W
CONFIDENTIAL

OCT 23 1981

OPERATOR: Donald C. Slawson
200 Douglas Building
Wichita, Kansas 67202

LEASE: #1 Renick 'V'
C SW NE of Sec. 29-25-29W
Gray County, Kansas

CONTRACTOR: Slawson Drilling Co., Inc.
200 Douglas Building
Wichita, Kansas 67202

COMMENCED: March 24, 1979

COMPLETED: April 5, 1979

CASING: Surface - 8 5/8" @ 410' w/325 sx 60/40 poz

State Geological Survey
WICHITA BRANCH

0 - 325 Sand and shale
325 - 415 Shale
415 - 675 Shale, chalk and sand
675 - 1120 Shale and sand
1120 - 1260 Shale and shells
1260 - 1445 Sand
1445 - 1721 Shale and shell with sand
1721 - 1760 Anhydrite
1760 - 1768 Shale
1768 - 2470 Shale and sand
2470 - 2500 Shale-Anhydrite
2500 - 2625 Lime and shells
2625 - 4265 Lime and shale
4265 - 4635 Lime
4635 - 4803 Lime and shale
4803 - 4840 Lime
4840 - 4995 Miss.
4995 - 5060 Miss.-Lime
5060 RTD

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS.

I, R.J. THATCHER, of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Renick 'V' test.


R.J. THATCHER

Subscribed and sworn to before me this 22nd day of April, 1979.