

WELL COMPLETION REPORT AND DRILLER'S LOG

State Geological Survey
WICHITA BRANCH

S. 28 T. 25 R. 29 W

API No. 15 — 069 — 20,120
County Number

Loc. SW SW

County Gray

Operator
Gear Petroleum Co., Inc.

Address
300 Sutton Place, Wichita, Kansas 67202


Well No. 1 Lease Name Three I. Inc.

Footage Location
660 feet from (S) line 660 feet from (W) line

Principal Contractor Slawson Drilling Co. Geologist Benny Singleton

Spud Date 5-14-81 Date Completed 5-23-81 Total Depth 5000 P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser Koch



Elev.: Gr. 2678

DF KB 2684

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8		409		275	
Production	7 7/8	4 1/2	10.5	4960	Common	125	None

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3	Jet	4848-4852

TUBING RECORD

Size	Setting depth	Packer set at
2	4850	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1000 gal. MCA; 1000 reg. 6000 MOD 202, 1000 reg	4848-4852

INITIAL PRODUCTION

Date of first production 6/5/81	Producing method (flowing, pumping, gas lift, etc.) Pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil 115 bbls.	Gas TSTM MCF	Water TRACE	Gas-oil ratio bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s) 4848-4852		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
GEAR PETROLEUM CO., INC. DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name
Three I, Inc. Oil

S 28 T 25 R 29 ²⁵ W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 45-60-60-90, strong blow Rec. 1160' GIP, 460' TF, 24' GOCM, 60' HGOCM, 315' F. Oil, 61' wtr. FP 59-147, 147-206, SIP 792-763	4824	4871	LOG TOPS	
			Anhydrite	1715 +969
			B/Anhydrite	1773 +911
			Heebner	4001 -1317
			Toronto	4015 -1331
			Lansing	4085 -1401
			Cherokee	4654 -1970
			Ste. Gen.	4784 -2100
			St. Louis	4838 -2154
			"C" Zone	4931 -2247
			LTD	5003 -2319
RTD	5000 -2316			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<div style="text-align: right; margin-bottom: 10px;"> _____ Jim Thatcher Signature Engineer </div> <div style="text-align: right;"> Title _____ 6/8/31 Date </div>
---------------	--

28?

33-25-29W

State Geological Survey
WICHITA BRANCH

DRILLERS LOG

OPERATOR: Gear Petroleum, Inc.
300 Sutton Place
Wichita, Kansas 67202

WELL NAME: Three I, Inc. #1
C SW SW Sec. ~~33~~-25S-29W Sect. 29?
Gray County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
200 Douglas Building
Wichita, Kansas 67202

COMMENCED: 5/14/81

COMPLETED: 5/23/81

RTD: 5000'

SURFACE CASING: 406' previously set in place by Henkle Drilling


PRODUCTION CASING: 4-1/2" set at 4960' with 125 sx

406' to 1780' Sand & Shale
 1780' to 2120' Shale & Lime
 2120' to 2782' Lime & Shale
 2782' to 3025' Shale & Lime
 3025' to 4585' Lime & Shale
 4585' to 4720' Lime
 4720' to 4815' Lime & Shale
 4815' to 4871' Mississippian Lime & Shale
 4871' to 5000' Mississippian Lime
 RTD 5000'

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state the above is an accurate copy of the Three 'I' Inc. log for Gear Petroleum Company, Inc.


 James C. Remsberg