

19-25-30W

WELL L *State Geological Survey*
WICHITA BRANCH

WELL NAME: Renick #2

OPERATOR: Continental Energy

SPUD DATE: 3-28-81

CONTRACTOR: Ramco Drilling Co.

COMPLETION DATE: 4-10-81

CASING: Set @ 1181' w/ 8 5/8". 500sx
light, 1/4% floreal, 2% cc
150 sx C. 2%cc 1/4% floreal.

LOCATION: NE/4 Sec. 19-T25S-R30W.
Finney Co., KS.

Prod. Csnq. 4507' of new 5 1/2
casq w/ 250 sx of Halco Lite
and 250 sx of 50/50 posmix.
April 10, 1981

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand	0'	200'
Sand and shale	200'	1165'
Shale	1165'	1195'
Sand and shale	1195'	1520'
Shale and sand	1520'	1836'
Annhydrite?	1836'	1865'
Shale with lime stks.	1865'	2285'
Shale	2285'	2440'
Shale and lime	2440'	2810'
Lime and shale	2810'	3037'
Shale and lime	3037'	3080'
Lime and shale	3080'	3430'
Shale and lime	3430'	3570'
Lime and shale	3570'	4882'
Lime	4882'	5010'
RTD	5010'	

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1981
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS

COUNTY OF SEDGWICK