

15-055-20184
9-25-31W

State Geological Survey
WICHITA BRANCH

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Reed #2
55' NW of C-SW Sec 9-25S-31W
Finney County Kansas

Commenced: 3-11-75

Completed: 3-16-75

OPERATOR: D. W. MARDEN

Depth		Formation	Remarks
From	to		
0	223	Sand	
223	335	Surface Clay-Sand	Ran 9 jts of used 28# 8 5/8"
335	1125	Shale	8V Thread csg set @ 330'
1125	1346	Shale-Redbed-Sand	Cemented w/250 sks Class H
1346	1810	Sand	2% Gel - 3% CC PD @ 4:55am.
1810	1838	Sand-Redbed	3-13-75 - 1" w/200 sks
1838	1855	Cismaren	2% CC Job Complete @
1855	2034	Shale-Redbed	1:00 p.m. 3-12-75
2034	2432	Shale-Lime	
2432	2499	Lime Shale	
2499	2575	Lime	
	2575 TD		Ran 82 jts of 4 1/2" csg set @ 2572' Cemented w/150 sks 50/50 Posmix 10% Salt P.D. @ 3:00 p.m. 3-16-75

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled 55' NW of C-SW Sec 9-25S-31W Finney County Kansas to the best of my knowledge and belief.


JAMES S. SUTTON II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 18th day of March, 1975, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the