

KANSAS DRILLERS LOG

API No. 15 — 055 — 20,326
County Number

Operator
McKelvy Oil Company

Address
48 Lloyd Drive Atherton, California 94025

Well No. #15 Lease Name
~~DEYK~~ C O R L E Y

Footage Location
1,320 feet from (N) (S) line 1,270 feet from (E) (W) line

Principal Contractor B. & N. DRILLING Geologist ROBERT POSEY

Spud Date 10/17/78 Total Depth 2,700 KB P.B.T.D.


Date Completed 10/20/78 Oil Purchaser

S. 15 T. 25 R. 31 ^K/_W

Loc. 50' NW/C NW

County Finney

640 Acres
N



Locate well correctly
Elev.: Gr. 2915

DF _____ KB 2923

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	12 1/4"	8-5/8"		369 KB	Class H	200	3% C C
PRODUCTION	7-7/8"	5 1/2"	15.5	2699 KB	Class H	650	

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
2	Dyna Jet	10'

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
ACIDIZE - 500 GAL 1590 - 7 1/2 BPM - 75 BBLs Total	2537 - 2547
FRAC - SLICK WATER - 600 GAL 15% - 12000# 10/20 490 BBLs.TOTAL	2537 - 2547

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.) OPEN FLOW				
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas 500 MCF	Water 0 bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold) VENTED			Producing interval(s)		

Operator MCKELVY OIL COMPANY

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

GAS

Well No. 15

Lease Name CORLEY

S 15 T 25 R 31 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

SAND

0

205

SHALE

205

1080

SHALE/LIME

1080

1740

SHALE

1740

1960

SHALE/LIME

1960

2700

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

A. P. McKelvy
Signature

Operator
Title

12/28/78
Date