

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

18-25-31W

Company- PETROLEUM, INC. & SKELLY OIL CO.

Farm- Kicks "C"

No. 1

SEC. 18 T. 25 R. 31W

C N $\frac{1}{2}$ N $\frac{1}{2}$ SW

2310' FSL 1320' FWL SW

Hicks "C"

CORRECTED LOG.

Total Depth. 2614'

Comm. 11-11-54

Comp. 11-16-54


Shot or Treated.

Contractor. Garvey Drlg. Co.

Issued. 6-15-57

County Finney

KANSAS



Elevation. 2826' KB

Production. 5,030,000 Gas.

CASING:

8 5/8" 397' w/300 sx cem.

5 1/2" 2596' w/500 sx cem.

Figures indicate Bottom of Formations.

sand-shale	260
shale-shelle	900
red bed-shale	1360
sand	1535
red bed-shale-shells	1660
red bed-shale	1725
salt-shale	1815
shale-shells	1875
Anhydrite	1883
lime-shale	2598 RTD
lime	2614

Total Depth

TOPS: SCHL.

B/Blaine 1296

Anhydrite 1798

B/Anhydrite 1880

Hollenberg 2464

Herington 2507

U. Krider 2532

L. Krider 2567

Winfield 2600

ACID TREATMENT:

No. 1 - Between 2597-2614' w/500 gals.

No. 2 - Between 2597-2614' w/2000 gals.

No. 3 - Between 2540-2575'

ACID-FRAC TREATMENT:

No. 1 - Between 2597-2614' w/2000 gals.

No. 2 Between 2540-2575' w/500 gals.

SI 72 hrs., CP-414#, open 20 min.,
6.6" mercury in 4" for 5,030, MCFG