

503 East Murdock,

Wichita, Kansas


31-25-31W

Company- PETROLEUM, INC. & SKELLY OIL CO.  
Farm- Vanderee Gas Unit No. 1

SEC. 31 T. 25 R. 31W  
C NW<sup>1</sup>/<sub>4</sub>

CORRECTED LOG.

County Finney  
KANSAS



Elevation. 2853' RB

Production. 7,100,000 CFG

Total Depth. 2655'

Comm. 12-17-54

Comp. 12-22-54

Shot or Treated.

Contractor. Garvey Drlg. Co.

Issued. 6-15-57

CASING:

8 5/8" 400' w/300 sx cem.

5 1/2" 2653' w/550 sx cem.

Figures indicate Bottom of Formations.

sand	105
sand	350
clay	400
shale-sand	570
shale-shells	875
red bed-shale	1210
Anhydrite	1235
shale-shells	1450
shale	1600
sand	1700
shale	1800
shale-sand	1900
shale	2240
shale-sand	2365
shale-shells	2490
shale-lime	2655
Total Depth	

TOPS:

B/Blaine	1329
Anhydrite	1848'
B/Anhdrite	1925
Hollenberg	2525
Herington	2568
U/Krider	2592
L. Krider	2630
Winfield	2660

Packer set : 2649' treated w/1000 gal. acid.

Acid treatment No.1 - Between 2653'-2668' reacidized w/5000 gals.

Acid treatment No.2 - Between 2653'-2668'

Acid treatment No.3 - Between 2602'-2640'

Acid -Frac No.1 -Between 2602'-2640'

Perf. 2646'-2647'

Perf. 2602'-2640'

Ran Gamma Ray.