

32-25-31W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL CO. & MICHAELIS DRIG.
Farm- Ralph Beach No. 1

SEC. 32 T. 25 R. 31W
C W/2 of Sec.

Total Depth. 2678'
Comm. 3-12-56 Comp. 3-16-56
Shot or Treated.
Contractor. Michaelis Drlg. Co.
Issued. 6-2-56

County Finney
KANSAS



CASING:
8 5/8" 507' cem w/300 sx
5 1/2" 2670' cem w/400 sx

Elevation. 2819'

Production. 8,983,000 CFG

Figures indicate Bottom of Formations.

soil and clay	40
sand	200
sand and shale	375
shale	845
red bed	970
red bed and sand gyp	1380
sand	1558
red bed and gyp	1683
shale, salt and gyp ✓	2195
shale and gyp	2270
red bed and anhydrite	2375
anhydrite and shale	2520
dolomite, sand & shale	2640
dolomite & shale	2678
Total Depth	

Tops:
Herington 2570
Upper Krider 2595
Lower Krider 2619
Winfield 2668

Ran Halliburton Electric log.

Treated Winfield formation with 1000 gallons of acid.

Acid treatment between 2670' and 2678'
Tested no gas and 25 gallons of water.

Producing Formation Hugoton Gas Pay