

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-055-20301

API No. 15 — 055 — 20,301
County Number

S. 34 T. 25 R. 31 ^N/_W
Loc. 495' FNL & 150' FEL SW
County Finney

Operator
Continental Energy

Address
South Star Route Garden City, Kansas 67846


Well No. # 1 Lease Name Minter-Wilson

Footage Location
495' feet from (N) line 100' feet from (E) line SW/4

Principal Contractor B & N Drilling Co. Geologist Raymond Palmer

Spud Date April 8, 1978. Total Depth 2670' P.B.T.D. 2661'

Date Completed April 22, 1978. Oil Purchaser Gas well



Locate well correctly
Elev.: Gr. 2815
DF _____ KB 2822

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2	8 5/8	23 #	562	Pozmix Common	200 150	Calcium Ch. 2 % Calcium Ch. 3%
Production	7 7/8	5 1/2	14 & 17	2669	200 Pozmix		18 % Salt

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement
		NONE

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
2	4" DML Jet	2622 to 2630

TUBING RECORD

Size	Setting depth	Packer set at
1 1/4 E.U.E.	2655'	NONE

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1000 Gal. 15 %	2622 to 2630
15,120 Gal 3 % Gelled acid, 10,000, 20-40 Frac sand	2622 to 2630

INITIAL PRODUCTION

Date of first production <u>Shut in gas well</u>		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

Continental Energy

DRY HOLE, SWDW, ETC.:
SIGW

Well No. 1

Lease Name Minter-Wilson

s 34 T 25 R 31 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Ran Schlumberger CNL-Den-GR-Cal			Stone Corral Herington Krider RTD	1898 2579 2610 2670

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Raymond E. Palmer
Signature

Geologist
Title

5-7-78
Date