

2 - 15 - 32W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- STANOLIND OIL & GAS CO.
Farm- Hicks Gas Unit "B" No. 1

SEC. 2 T. 25 R. 32W
SW SW NE
2490' S of NL, 2490' W of EL

Total Depth. 2622'
Comm. 12-5-54
Shot or Treated.
Contractor.
Issued. 1-29-55

Comp. 1-5-55

County Finney
KANSAS



CASING:
8 5/8" 920' com w/500 sx
5 1/2" 2607' com w/800 sx

Elevation. 2839' DF

Production. 20 Min. Open Flow
4,169,000 MCF Gas

Figures Indicate Bottom of Formations.

surface sand	40
sand - gravel	171
sand-blue clay - shale	588
blue clay - shale	880
red bed	1418
anhydrite	1630
shale - anhydrite	1810
anhydrite	1871
shale - anhydrite	2200
lime	2622
Total Depth	

Tops:	
Herington	2544
Krider	2572
Winfield	2607

Schlumberger ran Gamma Ray & Micro Log.
Ran 1 1/4" Tubing set at 2619'.

Acid Engineers acidized as follows:

Treated Winfield w/250 gal Jetrawash,
2000 gal gel 10% w/4000# sand, 1000
gal Jetrawash, flushed w/2500 gal water.

Treated Herington-Krider w/250 gal Jetrawash,
5000 gal gel 10% w/10,000#sand, 2500 gal
Jetrawash, flushed w/2500 gal water.

Perforating Guns Atlas Corp. perforated
w/6 shots per foot as follows:

2546-48', 2550-82'.

20 Min. Open Flow 4,169,000 MCF, SIP 315#