


7-25-32W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MAGNOLIA PETRO. COMPANY
Farm- John H. Burnside "BNo. 1

SEC. 7 T. 25 R. 32W
NW NW SE

County Finney KANSAS



Elevation. 2898 DE

Production. Open flow 9,680,000
Gas

Figures indicate Bottom of Formations.

surface sand & clay	170
shale & sand	245
shale	590
shale & sand strks	770
shale & shells	950
shale	970
red bed	1285
anhydrite	1330
red bed & shale	1500
sand	1675
shale & shells	1900
lime & shale	2659
sand & shale	2690
lime & shale	2800
Total Depth	

Tops:

Herington	2529 ?
Krider	2549
Winfield	2621
Towanda	2683
Ft. Riley	2729

Perf. 2606-2700' w/72 sh.,
NS. Acidized w/7000 gals.
SSG. Set plug 2681, perf.
2666-78' w/48 sh., SSG,
Acidized w/7000 gals. test
500 MCF Set plug 2641, perf.
2620-36 w/72 sh., NS,
acidized w/7000 gals., test
760 MCF Drld plug 2641, set
plug 2615, perf. 2606-14 w/24
sh., SSG.
Acidized w/7000 gals. test
1000 MCF.
Drld. plug 2615, set plug 2598,
perf. 2578-96' w/72 sh., NSG.
Acidized w/7000 gals. test 720 MCF
Drld plug 2598, set plug 2571,
perf. 2550-70 w/72 sh.
Acidized w/7000 gals., test 2500
MCF. Drld. plug 2571