

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

22-25-32W

Company- STANOLIND OIL & GAS CO.
 Farm- Hicks Gas Unit No. 1

SEC. 22 T. 25 R. 32W
 SW SW SW NE

2490' S of NL, 2490' W of EL

Total Depth. 2628

Comm. 2-21-54

Comp. 3-11-54


Shot or Treated.

Contractor.

Issued. 10-9-54

County Finney

KANSAS



Elevation. 2865 DF

8 5/8 @ 966' w/ 500 sx cmt.
 5 1/2 @ 2602' w/ 800 sx cmt.

Production. 4,169,000 Gas

Figures Indicate Bottom of Formations.

surface sand	30
sandy shale	460
shale	925
red bed	1040
red bed & shale	2010
shale	2370
shale & anhydrite	2480
shale & lime	2628
Total Depth	

TOPS:

Herington-Krider	2541
Winfield	2602

Schlumberger ran Gamma Ray, Microlog

Perf. 6 SPF

Herington-Krider 2547-66, 2571-81

Acidized

Winfield 2500 gal 15%

Herington-Krider 3000 gal 15%

All zones 13000 gal 7 1/2%