

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas

27-25-32W

Company- STANOLIND OIL & GAS CO.
Farm- Nusser Gas Unit No. 1
"A"

SEC. 27 T. 25 R. 32W

SW SW SW NE


2490' S of NL, 2490' W of EL

Total Depth. 2652
Comm. 2-13-54
Shot or Treated.
Contractor.
Issued. 10-9-54

Comp. 2-26-54

County Finney

KANSAS



CASING:
8 5/8 @ 966' w/ 500 sx cmt.
5 1/2 @ 2627' w/ 800 sx cmt.

Elevation. 2879 DF

Production. 1,917,000 Gas

Figures Indicate Bottom of Formations.

surface clay & sand	40
sand & gravel	450
clay & shale	920
red bed	1220
red bed & gyp	1340
gyp	1520
gyp & shale	2034
shale, gyp & anhydrite	2215
shale & anhydrite	2405
shale & lime	2450
lime	2652
Total Depth	

TOPS:
Herington-Krider 2568
Winfield 2627

Schlumberger ran Gamma Ray, Microlog

Perf. 6 SPF
Herington-Krider 2580-92, 2594-96,
2599-2601, 2609-13

Acidized
All zones 2500 gal 15%
Herington-Krider 2000 gal 15%
All zones 13000 gal 7½%