

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


1-25-33W

Company. SOCONY MOBIL OIL CO., INC.
Farm. State Tract 12 No. 1

SEC. 1 T. 25 R. 33W
C SE NW

Total Depth. 5241'
Comm. 10-27-61 Comp. 11-28-61
Shot or Treated.
Contractor. Peel Bros., Inc.
Issued. 8-11-62

County Finney
KANSAS



CASING:

Elevation. 2894.1' CE

8 5/8" @ 1570' w/1000 sks.

Production. DRY & ABND.

Figures indicate Bottom of Formations.

sand & shale strks.	425
shale	600
shale, shells & sand	805
sand, shale & Pyrite	995
red bed & shale	1110
shale	1305
Anhydrite	1330
shale	1415
sand	1550
sand, shale & lime shells	1650
shale & shells	1928
shale & lime	2105
lime & shale	2285
lime	2485
lime & shale	2822
shale & lime	2895
lime & shale	3038
lime shells & shale	3105
lime & shale	3250
shale, lime shells	3280
lime	3340
lime & shale	3465
lime	3875
lime & shale	3985
lime	4731
lime- cherty strks.	4756
lime	4852
lime & shale	4884
lime	5241
TOTAL DEPTH	

TOPS: SCOUT

Chase	2541
Winfield	2600
Council Grove	2832
Admire	3078
Wabaunsee	3232
Shawnee	3562
Heebner	3899
Lansing	3949
Kansas City	4179
Marmaton	4490
Cherokee	4620
Morrow	4823
Mervecian	4930