

5-25-33W

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.

SEC. 5 T. 25 R. 33W

FARM Spratt #B

NO. 1

LOC. NE NE NE SW

100' S. & 100' W of Center

TOTAL DEPTH 2730

COMM. 10-4-49

COMP. 10-9-49


SHOT OR TREATED

CONTRACTOR Corbett & Barbour Drlg. Co.

ISSUED 5-26-51

COUNTY Finney

KANSAS



CASINO

8 5/8" 730' cem. w/325 sx

5 1/2" 2729' cem. w/700 sx

ELEVATION 2917

PRODUCTION 17,000,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

sand & shale	625
lime, shells & shale	700
shale	730
shale & shells	850
red bed & sand	1100
sand & shale	1425
salt & shale	1600
shale & shells	1860
shale & sand	1955
anhydrite	2100
shale & shells	2345
shale & lime	2560
lime & shale	2640
shale & lime	2730
Total Depth	

Tops:	
Herington	2516
Upper Krider	2546
Lower Krider	2564
Winfield	2592
Upper Ft. Riley	2658
Lower Ft. Riley	2722

Perf:	
30 shots	2552-58
60 "	2564-76
30 "	2594-2600
60 "	2606-18
160 "	2658-90

S.I.P. 410.7