

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

15-25-33W

COMPANY CITIES SERVICE OIL CO.

SEC. 15 T. 25 R. 33W

LOC. NE NE NE SW

FARM Tait "E"

NO. 1

200' S. & 200' W. of Center

TOTAL DEPTH 2705

COMM. 11-15-49

COMP. 11-20-49


SHOT OR TREATED

CONTRACTOR Corbett & Barbour Drlg. Co.

ISSUED 5-26-51

COUNTY Finney

KANSAS



CASING

8 5/8" 765' cem. w/325 sx

5 1/2" 2704' cem. w700 sx

ELEVATION 2911

PRODUCTION 7,730,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

sand & shale	560
sand shells	725
shale	765
shale, sand & red bed	1225
shale & shells	1375
salt & shale	1895
shale & shells	2260
shale & lime	2590
lime	2705
Total Depth	

Tops:

Herington	2506
Upper Krider	2537
Lower Krider	2558
Winfield	2590
Upper Ft. Riley	2640

Perf:

80 shots	2536-52
80 "	2558-74
130 "	2590-2616
50 "	2650-60
70 "	2668-82

S.I.P. 412.8#