

16-25-33W

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.

FARM McWilliams #FH NO. 1

SEC. 16 T. 25 R. 33W

LOC. NE NE NE SW

100' S. & 100' W of cen.

TOTAL DEPTH 2705

COMM. 11-8-49

COMP. 11-13-49


SHOT OR TREATED

CONTRACTOR Corbett & Barbour Drlg. Co.

ISSUED 5-26-51

COUNTY Finney

KANSAS



CASINO

8 5/8" 765' cem. w/325 sx

5 1/2" 2704' cem. w/392 sx

ELEVATION 2922

PRODUCTION 17,800,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

sand	125
sand & shale	575
sand shells	725
shale	765
shale, sand & red bed	1120
shale & salt	1660
shale & lime shells	1915
shale & shells	2305
shale & lime	2500
lime	2595
shale & lime	2705
Total Depth	

Tops:	
Herington	2500
Upper Krider	2531
Lower Krider	2552
Winfield	2584
Upper Ft. Riley	2644

Perf:	
100 shots	2530-50
60 "	2556-68
40 "	2584-92
60 "	2598-2610
30 "	2646-52
100 "	2660-80

S.I.P. 426.0