

17-25-33W

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.

SEC. 17 T. 25 R. 33W

FARM Spratt "D"

NO. 1

LOC. NE NE NE SW

100' S. & 100' W. of Center

TOTAL DEPTH 2705

COMM. 11-1-49

COMP. 11-7-49


SHOT OR TREATED

CONTRACTOR Corbett & Barbour Drlg. Co.

ISSUED 5-26-51

COUNTY Finney

KANSAS



CASING

8 5/8" 805' cem. w/325 sx

5 1/2" 2704' cem. w/700 sx

ELEVATION 2940

PRODUCTION 7,150,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

sand	220
sand & shale	805
shale & red bed	1050
shells & sand	1405
salt & shale	1620
shale & shells	2460
shale & lime	2665
lime	2705
Total Depth	

Tops:	
Herington	2510
Upper Krider	2538
Lower Krider	2562
Winfield	2592
Upper Ft. Riley	2642

Perf:	
80 shots	2540-56
60 "	2564-76
60 "	2606-18
50 "	2654-64
60 "	2672-84

S,I.P. 408.0#