

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

32-25-33W

COMPANY CITIES SERVICE COMPANY

SEC. 32 T. 25 R. 33W

FARM Engler #A# NO. 1


LOC. NE NE NE SW

100' S & 100' W of center

TOTAL DEPTH 2707
 COMM. 10-4-49 COMP. 10-10-49
 SHOT OR TREATED
 CONTRACTOR Corbett & Barbour
 ISSUED 5-26-51

COUNTY Finney

KANSAS



CASING

8 5/8" 760' cem w/326 sx
 5 1/2" 2706' cem w/700 sx

ELEVATION 2930

PRODUCTION I.P. 15,500,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

sand, shale	0-	500
gumbo & sand		642
gumbo & shale		760
shale		900
shale, red bed		1425
red bed		1560
red bed, shale		1705
shale, salt		1850
redbed, shale		1910
shale		2000
shale, lime		2551
lime		2707
Total Depth		

Tops:
 Herington 2508
 Upper Krider 2544
 Lower Krider 2564
 Winfield 2594
 Upper Ft. Riley 2660

Perf:
 80 Shots 2540-56
 70 " 2562-76
 30 " 2592-98
 60 " 2604-16
 90 " 2650-68
 40 " 2672-80

I. P. 15,500 MCF SIP
 396.4