

35-25-33W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company-G. S. DAVIDSON

Farm- F. Drussell

No. 1

SEC. 35

T. 25

R. 33W

NE NE NE SW

100 S & W of center

Total Depth. 2646

Comm. 12-27-52 Comp. 3-18-53


Shot or Treated.

Contractor. Ben F. Brack Oil Co., Inc.

Issued. 12-5-53

County Finney

KANSAS



CASING:

9 5/8" 430' cem w/250 sx

6 5/8" 2619' cem w/800 sx

Elevation. 2900 D.F.

Production. 10,200,000 gas

Figures indicate Bottom of Formations.

sand & gravel	130
sand	320
shale sdy blue	400
shale blue	430
shale	489
shale blue	813
red bed	1270
red bed, shale	1688
shale, shells	2375
lime, shale	2495
shale, anhydrite	2575
lime, shale	2620
lime sandy	2635
lime	2646
Total Depth	

Tops:

Herrington 2562

Krider 2580

Winfield 2618

72 hr sut in - 20 minute

open flow Tested 10,200 MCF