

Driller's Log

24-25s-35w

STRATIGRAPHIC CORRELATIONS

McCoy Wildcats
February 8, 1988

15-093-20915

<u>Well/Location:</u>	McCoy Petroleum #1-21 Brown "M" 21-T25S-R34W C NW NE	McCoy Petroleum #1-4 Brown-Wms. 4-T25S-R34W NW NW SW	McCoy Petroleum #1-24 Tate "V" 24-T25S-R35W NE NE SW	McCoy Petroleum #1-4 Yeiser "A" 4-T26S-R34W C NE SW
KB Elevation	2965'	2970'	2988'	2969'
Surface Csg.	1801'	1904'	1910'	1868'
<u>Formation:</u>				
B. Cimarron Anh.	1872' (+1093) 293	1900' (+1070) 229	1902' (+1086) 261	1874' (+1095) 319
Wellington	2165' (+ 800) 301	2129' (+ 841) 347	2163' (+ 825) 312	2193' (+ 776) 297
Herington	2466' (+ 499) 55	2476' (+ 494) 56	2475' (+ 513) 55	2490' (+ 479) 57
Winfield	2521' (+ 444) 222	2532' (+ 438) 219	2530' (+ 458) 220	2547' (+ 422) 219
Council Grove	2743' (+ 222) 236	2751' (+ 219) 229	2750' (+ 238) 230	2766' (+ 203) 232
Admire	2979' (- 14) 203	2980' (- 10) 212	2980' (+ 8) 201	2998' (- 29) 194
Wabaunsee	3182' (- 217) 289	3192' (- 222) 288	3181' (- 193) 285	3192' (- 223) 294
Topeka	3471' (- 506) 333	3480' (- 510) 322	3466' (- 478) 332	3486' (- 517) 337
Heebner	3804' (- 839) 86	3802' (- 832) 96	3798' (- 810) 94	3823' (- 854) 101
Lansing	3890' (- 925) 218	3898' (- 928) 146	3892' (- 904) 209	3924' (- 955) 208
Kansas City	4108' (-1143) 291	4044' (-1074) 334	4101' (-1113) 283	4132' (-1163) 294 DST 1
B. Kansas City	4399' (-1434) 30	4378' (-1408) 23	4384' (-1396) 24	4426' (-1457) 21
Marmaton	4429' (-1464) 126 DST 1(S) & 2	4401' (-1431) 121	4408' (-1420) 124 DST 1(S)	4447' (-1478) 121 DST 2
Cherokee	4555' (-159 0) 217	4522' (-1552) 212	4532' (-1544) 220	4568' (-1599) 219 DST 3
Atoka	4772' (-1807) 57	4734' (-1764) 62	4752' (-1764) 56	4787' (-1818) 51
Morrow	4829' (-1864) 123 DST 3(S)	4796' (-1826) 144 DST 1 & 3(P)	4808' (-1820) 182 DST 2(*)	4838' (-1869) 88 DST 4(S*) DST 5(S*)
Chester	--None--	--None--	--None--	--None--
St. Genevieve	4952' (-1987) 26	4940' (-1970) 35 DST 2 & 3(P)	4990' (-2002) 13 DST 2	4926' (-1957) 110
St. Louis	4978' (-2013) 247 DST 4(S*)	4975' (-2005) 225 DST 2, 3 & 4	5003' (-2015) 247 DST 2 & 3(SP)	5036' (-2067) 224 DST 6
TOTAL DEPTH	5225' (-2260)	5200' (-2230)	5250' (-2262)	5260' (-2291)
IPP	183 BOPD N.W. St. Louis	D & A Perf. L. Morrow & St. Genevieve	172 BOPD L. Morrow	M. & L. Morrow

KEY: * = Productive; P = Perforated; S = Show