

✓

7-314W MAP NO. 78 SEC. 5-25S-35W

STATE Kans COUNTY Kearny LOC. C SE/4

OPER. Kansas Natural Gas, Inc., Hays, Kansas FT/FR _____ LINE _____

WELL #1 FARM Frost "A" FT/FR _____ LINE _____

FIELD Hugoton Field ELEV. 2993 GR. 3000 DF. 3003 KB _____

INT. Graham Michaelis Drlg. GEOL. _____

CO. INT. 2700' Gas Test

F.R. 6/11/63 SPUD 6/12/63 COMP. 7/30/63

TD 2670 FM. Chase Gr. PBD. 2640

Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
		<u>Chase Group</u>	<u>2425-2621</u>		<u>400 5000 A & Frac</u>
	<u>I.P Gauge: 22,000,000 Cfgpd (Press N.A.)</u>				
Casing Record	<u>10-3/4" @612' w/400 sx</u>		<u>7" @2669' w/1000 sx</u>		<u>Data Inc.</u>

(KB) Log

U/Kri 2425 + 578 L/FR 2595 + 408 RTD 2670, Log, 7" @2669' w/
 L/Kri 2442 + 561 LTD 2670 + 333 1000 sx, MICT, CO 2640 PBD
 Winf 2477 + 526 RTD 2670 + 333 Perf 44/2425-36 (U/Kri), 64/
 U/FR 2541 + 462 2442-56 (L/Kri), 68/2479-96
 (Winf), 120/2542-72 (U/FR),
 4/2595-2621 (L/FR), 5000 A, \$ 1d, Ga (est) 4,500,000 Cfgpd,

Frac (140,000 GW x 140,000# Sd), \$ & Flow 1d, Ga 22,000,000 Cfgpd,
 No Press Avail, Chase Group 2425-2621.

COMPLETED (7/22/63)

Liberal Laps

3003 KB

Winfeld 2478 + 525

TD 2673

¢ 22,000 MCF