


10-88W Map No. 78
 OPER KANSAS NEBRASKA NAT GAS
 HASTINGS, NEBR
 #4-A CAMPBELL
 EARL F. WAKEFIELD
 HUGOTON FIELD (CHASE GAS)
 CO BD GA 12,012,000 CFGPD + LOAD
 CHASE GR 2440-2640 API #15-093-20015



S-T-R 6-25S-35W
 SPOT APP W $\frac{1}{2}$ SW NE
 CO KEARNY, KS
 ELEV 2988 KB

2-S 2986 DF

KB LOG TOPS

UK HERR 2438 + 550
 KRI 2454 + 534
 WIN 2496 + 492
 U/FR 2547 + 441
 L/FR 2610 + 378
 LTD 2660 + 328
 RTD 2660 + 328
 TD IN FR FORM

SPUD 8-25-68 10 3/4" 556/500 SX GEOL - LAWRENCE HOLMSTROM

NO CORES, NO DSTS, RTD 2660, LOG, 7" 2659/1000 SX

MICT, CO & PERF 33/2440-51 (HERR) 42/2456-70 (KRI)
42/2498-2512 (WIN) 90/2550-80 (FR) 90/2610-40 (L/FR)
 FRAC W/200,000# SD + 200,000 GAL GELL WTR,
 CO BD GA 12,012,000 CFGPD + LOAD, CHASE GR 2440-2640
COMPLETED 10-8-68

Hor 2406

COMP ISSUED 10-11-68