


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- EXCELSIOR OIL CORPORATION
Farm- Schaffer No. 1

SEC. 34 T. 25 R. 36W
C SW NW

Total Depth. 5150'
Comm. 5-22-57 Comp. 6-14-57
Shot or Treated.
Contractor. Honaker-Davis Drlg. Co.
Issued. 1-25-58

County Kearney
KANSAS



CASING:
13 3/8" 527' cem w/500 sx
8 5/8" 2249' cem w/250 sx
5 1/2" 5149' cem w/250 sx

Elevation. 3056 RB

Production. 185 BOPD

Figures Indicate Bottom of Formations.

sand & gravel	50
gravel & sand	260
gravel	498
blue shale	600
shale & lime	690
lime & shale	720
red bed & shale	1035
red bed & lime	1220
red bed & Anhydrite	1265
red bed & shale	1515
salt & red bed	1550
red bed & shale	1565
shale & lime	1688
red bed & shale	1780
shale & salt	1815
lime & shale	1835
red bed, shale & lime	1980
shale & lime	2075
lime & shale	2212
lime	2250
Anhydrite & shale	2637
lime & shale	2722
shale & lime	2740
lime & shale	3123
lime, shale & Chert	3193
lime & shale	3388
lime, shale & chert	3424
lime & shale	3549
lime	3709
lime & shale	3777
lime & chert	3834
lime	3881
lime & shale	4052
lime	4103
lime & shale	4296
lime	4801
lime & shale	4880
lime	4903
lime & chert	5058
Chert & lime	5125
lime & Chert	5150 RTD
Total Depth	

TOPS:SCOUT	
Hollandale	2332
Herington	2364
Upper Krider	2393
Lower Krider	2414
Winfield	2456
Upper Ft. Riley	2510
Lower Ft. Riley	2558
Fl. Flint	2614
Wreford	2652
Council Grove	2690
Admire	2848
Wabaunsee	3064
Lansing	3813
Morrison	4737
Mississippian	