


666
150
4-18

90090 ✓

8-24W Map No. K-78
OPER EXCELSOR OIL CORP
HASTINGS, NEBR.
WELL #2 MASONIC HOME "A"
DR DAVIS DRLG. INC.
FIELD LAKIN FIELD (MISS OIL)
I.P. _____



S-I-R 34-25S-36W
SPOT C SW SE
CO KEARNY (KS)
ELEV 3044 KB
E 3040 DF (KB LOG)

D&A

SPD 7-15-66 8" @562' W/400 SX. WOODY PAUL-GEOL
RTD 5100' SCHLUMBERGER LOG
WLT #1 (ST L) 5012-14½ (2 CHAMBER TOOL) OP 1 HR, R 22 CC WTR,
(40% FM WTR) + 42,600 CC FM WTR, ISIP 900#/25", FSIP
975#/1 3/4 HRS.
WLT #2 (ST L) 5006-8½ (2 CHAMBER TOOL) OP 1 HR, R 2000 CC M
+ 200 CC WTR W/SLT TR OIL, ISIP LESS THAN EXPLOSION,
SP 90#, FSIP LESS THAN EXPLOSION
D&A 8-2-66 COMPLETED

C GR	2685 + 359
ADM	2870 + 174
NEVA	2990 + 54
HB	3734 - 690
TOR	3741 - 697
LAN	3815 - 771
MAR	4370 - 1326
MRW	4752 - 1708
STE G	4874 - 1830
ST L	4912 - 1868
LTD	5103 - 2059
RTD	5100 - 2056

Data Inc

MISCEL DATA	GEOL	<u>"WOODY" PAUL</u>	ELEV	<u>3041 DF</u>	SPUD DATE	<u>7-15-66</u>
	FTG	_____		<u>3035 GR</u>	DRLG COMP	<u>8-2-66</u>
	SUPPT	_____			FR by DATA	<u>6-27-66</u>
	CSG	<u>8" 562 W/400 SX.</u>			COMP by "	<u>8-4-66</u>

L-S 3038DF