

Company - STANOLIND OIL & GAS CO.  
Farm - C. A. Loucks No. 1

9-25-37W

SEC. 9 T. 25 R. 37W

SW SW NE

2490' SN1 & 2490' WE1 NE/C

Total Depth. 2710'  
Comm. 2-5-48 Comp. 2-25-48  
Shot or Treated. Acidized  
Contractor.  
Issued. 7-31-48

County. Kearny  
KANSAS



Elevation. 3196 Ind.

Production. 3,960,000 Gas

CASING:

10-3/4" 713' Cem. W/500 Sx.  
7" 2503' Cem. W/700 Sx.  
5" 2653'

Figures Indicate Bottom of Formations.

clay 62  
sand & gravel 175  
shale blue & shells 360  
sand & shale 655  
red bed 735

redbed sand, anhy.  
and gyp 1235  
redbed sand & shale 1585  
lime & red rock 1700  
red rock & anhydrite 2255  
red rock & shale 2320  
anhydrite 2395  
anhydrite & gyp 2450  
anhydrite RTE 2510  
lime 2530  
shale blue 2535  
red rock 2560  
shale blue 2563  
lime & sand 2580  
red rock 2595  
lime 2615  
red rock 2625  
shale blue 2635  
shale gy 2650  
red bed 2660  
shale gy 2670  
lime brkn 2710  
Total Depth

Schlumberger ran to 2708

All zones AW 2000 gals. 15%.  
4410 gal flush, Max treating  
pressure 600#. Broke to 300#.  
Time 21 min. All zones REAW  
14,500 gal, 15%, 12,500 gal  
flush Max treating pressure  
300#. No break. Time on acid  
19 min. On flush 26 min.

Tops:  
Herington-Krider 2502  
Winfield 2548  
Towanda 2601  
Ft. Riley 2653