

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 E. Murdock,

Wichita, Kansas

12-25-37W

Company - STANOLIND OIL & GAS CO.

Farm - Beymer Gas No. 1

Unit "A"

SEC. 12 T. 25

R. 37W

NE NW SE NW

Total Depth. 2624

Comm. 3-4-50

Comp. 3-27-50

Shot or Treated.

Contractor.

Issued. 6-3-50

County. Kearny

KANSAS



Elevation. 3069 Ind.

Production. 8,100,000 gas

CASING:

10 3/4" 660' cem. w/450 sx.
7" 2556' cem. w/300 sx.

Figures Indicate Bottom of Formations.

clay	40
sand	157
sand, clay	430
sand, shale	610
red bed	757
red bed, anhyd, gyp,	
sand	1390
anhyd., sand, salt	1541
red bed, anhyd., dolo.	
shale	1770
anhyd., shale	2086
shale	2243
lime, shale	2380
dolo.	2432
shale, lime	2566
lime	2624
Total Depth	

Tops:

Herington-Krider	2404-2436
Winfield	2458-2474
Towanda	2506-2538
Ft. Riley	2556-2596

T. D. 2624' Lane Wells tools Survey

Lane Wells perforated w/320 shots.

Chemical Process acidized w/19,000 gals. 15%.

Halliburton ran H-40 tool.