

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-25-37W

Company. STANOLIND OIL & GAS CO.
 Farm. Waechter Gas No. 1
 Unit "M"

SEC. 15 T. 25 R. 37W
 C E/2 SW NW SE
 1690' N of SL, 2000' W of EL

Total Depth. 2565

Comm. 1-2-54

Comp. 1-17-54

County Kearny

KANSAS

Shot or Treated.

Contractor. Noble Drilling Corp. & Manning Drilling Co.

Issued. 10-9-54



CASING:

8 5/8 @ 527' w/ 450 sx cmt.
 5 1/2 @ 2519' w/ 800 sx cmt.

Elevation. 3055

Production. 9.794,000 Gas

Figures Indicate Bottom of Formations.

surface sand & clay	40
clay & shale	480
red bed	800
gyp	1000
shale & gyp	1480
shale, anhydrite & gyp	1554
shale & anhydrite	2005
shale & lime	2338
lime	2565
Total Depth	

Perf. 6 SPF as follows:

2476-98, 2470-72, 2452-56, 2444-48,
 2433-38, 2420-28, 2394-2400, 2390-92,
 2376-84, 2366-74, 2362-64, 2358-60

Dolofrased as follows:

Treated Ft. Riley w/ 250 gal DF mixed
 w/ low tensio chem., 250 gal DF spacer,
 3000 gal 10% gel acid w/ 6000# sand,
 flushed w/ 250 gal DF spacer, 1500
 gal 7½% acid & 750 Gal DF.
 Treated Towanda w/ 250 gal DF mixed w/
 low tension chem., 250 gal DF spacer
 2500 gal 10% gel acid w/ 5000# sand,
 flushed w/ 250 gal DF spacer, 1250
 gal 7½% acid & 750 gal DF.
 Treated Winfield w/ 250 gal DF mixed
 w/ low tension chem., 250 gal DF spacer,
 2000 gal 10% gel acid w/ 4000# sand,
 flushed w/ 250 gal DF spacer, 1000 gal
 7½% acid & 750 gal DF.
 Treated Herington-Krider w/ 250 gal
 DF mixed w/ low tension chem., 250 gal
 DF spacer, 3000 gal 10% gel acid
 w/ 6000# #2 sand, flushed w/ 250 gal
 DF spacer, 1500 gal 7½% acid & 750
 gal DF.

TOPS:

Herington-Krider	2359
Winfield	2420
Towanda	2470
Ft. Riley	2518