

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

Company - STANOLIND OIL AND GAS COMPANY
Farm - Tate Gas Unit No. 1

SEC. 28 T. 25 R. 37W
SW SE NE NW
1250' SN1 & 2440' EW1 NWc

Total Depth. 2615'
Comm. 10-19-47 Comp. 12-3-47
Shot or Treated. Acidized w/2000 gals.
Contractor.
Issued. 1-3-48

County. Kearny

KANSAS



Rotary Tools: 0-2415'
Cable Tools: 2415-2615'

CASING:

10-3/4" 589' Cem. w/375 sx
7" 2409' Cem. w/350 sx

Elevation. 3105-9 Ind.

Production. 20 min. open flow
9,205,000 Gas

Figures Indicate Bottom of Formations.

sand	0-15
sand, clay blue & red	
bed	580
red bed	600
red bed & shale	770
red bed, anhydrite,	
shale & shells	1495
shale & lime	1845
shale, lime & shells	2200
shale, shells & lime	2405
lime & shale	2415
lime	2425
lime, shale & lime	
brwn	2471
lime	2484
red rock	2505
red rock & shale	2527
lime & shale	2549
shale, lime & shale	2575
shale & lime	2615
Total Depth	

Tops:

Herington-Krider	2407-2440
Winfield	2457-2484
Towanda	2505-2540
Ft. Riley	2562-2602