

33-25-37W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY


508 East Murdock,

Wichita, Kansas

Company- STANOLIND OIL & GAS CO.  
Farm- Waechter Gas Unit No. 1  
"J"

SEC. 33 T. 25 R. 37W  
NW SE NW SE  
800' S, 800' E of  
Center  
County Kearny  
KANSAS

Total Depth. 2565  
Comm. 6-12-51 Comp. 7-3-51  
Shot or Treated.  
Contractor.  
Issued. 12-15-51



CASING:  
10 3/4" 531' 400 sxs. cem.  
7" 2539' cem w/300 sxs.

Elevation. 3086  
3085 (ma)

Production. 9,978,000 gas

Figures Indicate Bottom of Formations.

surface sand, clay	100
clay	200
blue shale	310
blue shale, sand	465
blue shale, shells	485
red bed	620
red rock	1070
anhydrite	1130
red sand	1190
red rock	1380
salt, red rock	1505
red rock	1620
red rock, anhydrite	1775
anhydrite	1885
anhydrite, red rock	2020
red rock, shale	2055
red rock, anhydrite	2175
anhydrite, lime	2325
lime	2380
anhydrite, lime	2415
shale, lime	2510
lime	2565
Total depth	

Tops:	
Winfield	2434
Towanda	2492
Ft. Riley	2539