

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


2-25-38W

Company - MID-CONTINENT PETRO. CORP.
Farm H. A. Smalley "C" No. 1

SEC. 2 T. 25 R. 38W
NEc SW

Total Depth. 2560'
Comm. 9-6-48 Comp. 9-12-48 ✓
Shot or Treated.
Contractor. Noble Drlg. Corp.
Issued. 11-6-48

County. Kearney
KANSAS



CASING:

8 5/8" S.S.S.H. 581'
5 1/2" New S.S. 2546'

Elevation. 3132.2nd

Production. 4,665,000 Gas

Figures Indicate Bottom of Formations.

surface clay	34
shale and clay	90
water gravel	105
shale and clay	350
water gravel	380
shale and clay	540
red bed	593
redbed and sand	1112
gyp, sand, redbed and salt	1462
gyp, shale and salt	2027
redbed and shale	2185
shale	2320
dolomite & anhydrite	2385
Herington dolomite	2394
shale	2396
Krider dolomite	2412
shale	2434
Winfield dolomite	2463
shale	2484
Towanda lime	2516
shale	2545
Ft. Riley lime	2560
total depth	

Tops:

Herington	2385
Krider	2396
Winfield	2434
Towanda	2484
Ft. Riley	2545