

4-25-38W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - MID-CONTINENT PETR. CORP.
Farm - Ben Strobridge No. 1

SEC. 4 T. 25 R. 38W
SE SW NE

Total Depth. 2520
Comm. 9-23-49 Comp. 9-29-49
Shot or Treated. 23,00 gal.
Contractor. Noble Drilg. Corp.
Issued. 12-17-49

County. Kearny
KANSAS



Elevation. 3108 Ind.

Production. 2,670,000 gas

CASING:

8 5/8" 525'
5 1/2" 2475'

Figures indicate Bottom of Formations.

sand	55
shale	170
sand & clay	285
shale & gyp	405
sand	470
red bed	559
red bed, sand & gyp	1150
salt & shale	1520
shale & sand	1820
Anhyd.	2017
shale & anhyd.	2168
shale & lime	2325
lime	2335
shale	2337
lime	2348
lime & shale	2382
lime	2397
shale & lime	2438
lime	2452
lime & shale	2477
lime & dolo.	2520
Total Depth	

Tops: Schlumberger
Herrington 2325
Krider 2337
Winfield 2382
Towanda 2438
Pt. Riley 2477