

11-25-38 W

SEC. 11 T. 25 R. 387
NW SE NW SE
700' S. of NL 700' E. of WL SE $\frac{1}{4}$

County Kearny
KANSAS

8 5/8" 493: cem. w/250 sx
5 1/2" 2488: cem. w/250 sx

Elevation. 3091
3094/5d.
Production. 13,690,000 Gas

A 4x4 grid with a star-like shape in the bottom-right quadrant. The shape consists of a central point with several lines radiating outwards, resembling a stylized star or a cluster of lines.

Tops:	
Herington-Krider	2322
Winfield	2366
Towanda	2435
Ft. Riley	2488

Lane wells perforated w/6
shots per ft. as follows:

Winfield 2376-90!, 2403-09!,
2423-30!

Towanda 2437-40', 2443-51',
2456-62', 2466-74'.

Acid Engineers acidized as follows:

Ft. Riley	2500	gal.	15%
Horington-Krider	2500	gal.	15%
Winfield	2000	gal.	15%
Townsend	3000	gal.	15%
All Zones	24000	gal.	7 $\frac{1}{2}$ %