

12-25-38W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company. STANOLIND OIL & GAS CO.
 Form Beymer Gas Unit No. 1
 "D"

SEC. 12 T. 25 R. 38W

NE SW NE SW

700' S of NL, 700' W of EL

Total Depth. 2515

Comm. 6-3-52

Comp. 6-21-52


Shot or Tre. ted.

Contractor.

Issued. 7-4-53

County Kearny

KANSAS



Elevation. 3082

Production. 5,346,000 Gas

CASING:

8 5/8 set at 522' w/ 350 sx cement
 5 1/2 set at 2490' w/ 300 sx cement

Figures indicate Bottom of Formations.

sand & gravel	60
shale	430
shale & sand	470
red bed	950
anhydrite & red rock	1200
salt & red rock	1275
red rock	1425
anhydrite	1445
red rock	1500
anhydrite & red rock	2080
red rock	2140
anhydrite	2330
anhydrite & lime	2460
lime	2515
Total Depth	

TOPS:

Herrington-Krider	2331
Winfield	2376
Towanda	2440
Ft. Riley	2490

Schlumberger ram Gamma Ray & Micro
 Logs.

Perf. 6 SPF as follows:

Herrington-Krider, 2335-48, 2351-56,
 2359-66.
 Winfield, 2385-95, 2404-12, 2415-24,
 Towanda, 2445-55, 2457-70, 2476-82.

Acidized as follows:

Ft. Riley	2500 gals.	15%
Herrington-Krider	2500 gals.	15%
Winfield	2500 gals.	15%
Towanda	3000 gals.	15%
All zones	24000 gals.	7 1/2%