

20-25-38W

Company- STANOLIND OIL & GAS COMPANY
 Farm- May Beauty "E" No. 1

SEC. 20 T. 25 R. 38W
 150' N of SL
 150' E of WL NE $\frac{1}{4}$
 SW SW SW NE
 County Kearny
 KANSAS

Total Depth. 2555'
 Comm. ~~2-24-53~~
 Shot or Treated.
 Contractor.
 Issued. 4-11-53

Comp. ~~2-24-53~~

CASING:

8 5/8" 593' com w/400 sx.
 5 1/2" 2522' com w/900 sx

3173(m)

Elevation. 3170'
 3174(rod)

Production. 1,906,000 Gas

Figures Indicate Bottom of Formations.

sand	185
sand, blue shale	300
shale	400
shale blue	554
red rock	592
red bed, red rock	640
gyp., shale	800
shale	1100
salt	1170
anhyd.	1200
salt	1390
shale, shells	1475
anhyd.	1574
shale, shells	1800
sand	1845
shale	1849
anhyd.	1867
shale, shells	2212
shale	2225
shells, lime	2317
lime	2555
Total Depth	

Tops	
Herrington	2367
Winfield	2417
Towanda	2487
Ft. Riley	2522

Schlumberger ran Gamma Ray & Micro Log.

Late Wells perforated with 6 shots per ft. as follows:

Herrington-Krider - 2367-80', 2382-87', 2390-93', 2396-2402'.
 Winfield - 2418-24', 2426-29', 2432-39', 2441-46', 2470-72'
 2475-78', 2481-83'.
 Towanda - 2487-91', 2494-2502', 2507-10'.

Western Acid Co. acidized as follows:

Ft. Riley	2500 gals. 15%.
Herrington-Krider	2500 gals. 15%.
Winfield	2000 gals. 15%.
Towanda	2000 gals. 15%.
All zones	21000 gals. 7 1/2%.

Permanent bench mark 8.50' above side outlets on Braden Head.