

## WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY

508 East Murdock

Wichita, Kansas

24 - 25 - 38W

Company - STANOLIND OIL &amp; GAS COMPANY

Farm - Dale Gas Unit

No. 1

SEC. 24 T. 25 R. 38W

SW SW NE SW

1250' S of NL, 1250' W of EL,  
SW  $\frac{1}{4}$ 


County. Kearny

KANSAS

Total Depth. 2572  
 Comm. 5-30-51 Comp. 6-21-51  
 Shot or Treated.  
 Contractor.  
 Issued. 9-22-51

## CASING:

10 3/4" 544' cem w/450 sx  
 7" 2526' cem w/300 sx



3109(m)

Elevation. 3107

3110 (2nd)

Production. 17,885,000 gas

Open Flow 20 min.

Figures Indicate Bottom of Formations.

|                     |      |
|---------------------|------|
| sand                | 70   |
| sand, gravel        | 85   |
| clay                | 177  |
| shale blue          | 500  |
| shale blue, redbed  | 505  |
| red bed             | 600  |
| shale, gyp          | 2158 |
| shale, anhydrite    | 2300 |
| shale, gyp & anhyd. | 2354 |
| shale, anhyd.       | 2404 |
| shale, lime         | 2515 |
| lime                | 2572 |
| Total Depth         |      |

## Tops:

|                  |      |
|------------------|------|
| Herington-Krider | 2358 |
| Winfield         | 2410 |
| Towanda          | 2482 |
| Ft. Riley        | 2526 |

Ran Schlumberger to 2572 TD  
 Lane Wells Gun Perf. w/6 SPF:  
 Herington-Krider 2366-73  
 2394-2401  
 Winfield 2413-31  
 2434-39  
 Towanda 2488-2501

## Dowell Inc. Acidized:

Ft. Riley w/2500 gal 15%  
 flushed w/450 gal wtr.  
 Towanda w/1500 gal 15%  
 flushed w/600 gal wtr.  
 Winfield w/2500 gal 15%  
 flushed w/600 gal wtr.  
 Herington-Krider w/1500  
 gal 15% flushed w/600 gal  
 water.

All Zones w/10,000 gal 7 1/2%  
 flushed w/4120 gal water.

All Zones w/7000 gal 7 1/2%  
 flushed w/3750 gal water.

All Zones w/3500 gal 7 1/2%  
 flushed w/4000 gal water.