

28-25-38W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- STANOLIND OIL & GAS CO.
Farm- Max Cohen "A" No. 1

SEC. 28 T. 25 R. 38W
NE NE NE SW
150' S of the NL,
150' W of EL of SW $\frac{1}{4}$
County Kearny
KANSAS

Total Depth. 2588
Comm. 9-1-51
Shot or Treated.
Contractor.
Issued. 12-15-51

Comp. 9-14-51

CASING:

10 3/4" 566' cem w/400 sxs.
7" 2558' cem w/300 sxs.

Elevation. 3168
3171 (cond)
Production. 25,162,000 gas

Figures Indicate Bottom of Formations.

surface sand, clay	40
water, gravel, blue	
clay	100
gravel, shale, blue	
clay	280
blue clay	320
gyp, shale	390
shale, sand	525
red bed	700
gyp, shale	1050
anhydrite	1085
gyp, shale	1125
shale	1180
anhydrite	1202
shale	1410
anhydrite	1780
anhydrite, shale	1870
lime, shale	2177
lime	2588
Total depth	

4200 gal wtr.
2500-2541 w/2500 gal 15%
flushed w/600 gal wtr.
2459-2500 w/2000 gal 15%
flushed w/600 gal water
2418-2459 w/2000 gal 15%
flushed w/600 gal wtr.
2377-2418 w/2000 gal 15%
flushed w/600 gal wtr.
All zones w/13000 gal 7 1/2%
and 3250# XM-18, flushed
w/3000 gal wtr.
All zones w/9000 gal 7 1/2% and
XM 18, flushed w/3000 gal wtr.
All zones w/5000 gal 7 1/2% and
1250# XM 18, flushed w/3000
gal wtr.

Tops:
Herington-Krider 2388
Winfield 2444
Towanda 2512
Ft. Riley 2558

Schlumberger ran to 2588
Lane-Wells gun perforated
w/6 SPF as follows:
Herington-Krider 2388-2398

2402-2406
2410-2416
2426-2434

Winfield 2446-2456
2464-2478
2488-2496
Towanda 2512-2538

Dowell Inc. acidized as follows:
w/2500 gal 15% flushed w/